




KEITH_2K vs Other Urban Turbines

Southwest Windpower Skystream 3.7	Hetronix™ KEITH_2K	Fortis Montana
		
Type: Downwind rotor	Type: Upwind rotor	Type: Upwind rotor
Rated: 2.4 kW	Rated: 2.0 kW	Rated: 5.8 kW
Diameter: 3.72 m.	Diameter: 2.50 m.	Diameter: 5.00 m.
Max. Output kWh p/year: 3.600 kWh	Max. Output kWh p/year: 4.000 kWh	Max. Output kWh p/year: 7.520 kWh
Cut-in Wind Speed: 3.5 m/s	Cut-in Wind Speed: 3.0 m/s	Cut-in Wind Speed: 2.5 m/s
Rated Wind Speed: 13 m/s	Rated Wind Speed: 12.5 m/s	Rated Wind Speed: 10.0 m/s
Overspeed protection: stall regulation control	Overspeed protection: Active side furling protection + stall regulation control	Overspeed protection: short-circuit generator
Warranty: 5 years limited warranty	Warranty: 4 years Including comprehensive 3 years On-site ACTIVE Service Contract	Warranty: 5 years

Specification resources/data courtesy:

All Small Wind Turbines online, August 2008
Project Wineur, February 2007

and